NEW CARPARK
AREA (1353sq.m.)

49

3 Phase.

MARK OUT 1.50m WIDE ACCESS FOR PEDESTRIANS WITH THERMOPLASTIC LINE MARKING AS SHOWN.

EXISTING CONCRETE COLUMN

PROVIDE NEW BOLLARDS @1.8m Crs.

THERMOPLASTIC LINE MARKING

HATCHING TO THIS AREA

SECURITY PARKING

Proposed Data Hub.

Inverter

Generator

Electric Sub Station.

Connect to Exist. Gully

NORTH ENTRANCE

FORM NEW RAMP

EXISTING NORTH CARPARK. (975sq.m.)

NO ENTRY

MARK OUT 1.50m WIDE ACCESS FOR PEDESTRIANS WITH THERMOPLASTIC LINE MARKING AS SHOWN.

NEW SIGN POST 'STAFF PARKING ONLY'

MH

Connect to Existing Manhole

GRASS/ LANDSCAPING.

EGL 6.050

EXISTING LANDSCAPING RETAINED.

EXISTING BUILDING.

Double Row of Granite Cobble

SOUTH ENTRANCE

Two no. 100mm ducts to be brought into building at ground level beside existing column.

Granite Pavers

Granite Chamfered Kerb

Granite Landscape Kerb

Granite Water Channel

Raised Granite Cobble

Granite Cobble Bollards with 4 Reflective Panels

EXISTING CARPARK.

GRASS/ LANDSCAPING.

EGL 8.5M/ EGL 2.0M

P.G.L. -.150

FOOTPATH

EGL 8.5M/ EGL 3.0M

EXISTING CARPARK. ENTRANCE ROAD

Height Restriction for Lorrys and Vans

DRIVE WAY.

EGL 5.975

PROVIDE NEW GULLY

150mm Pipe

DISHED FOOTPATH FOR WHEELCHAIR / PRAM ACCESS.

T- Frame double Canopy.

FOOTPATH.

TARMAC FINISH.

CONC KERBING.

XISTING BUILDING.

3 Phase Electricity

1644m2 of pv panels

EV

GRASS/ LANDSCAPING.

PAVED AREA.

Granite Paving

Granite Chamfered Kerb

Granite Landscape Kerb

DISHED FOOTPATH FOR WHEELCHAIR / PRAM ACCESS.

DRIVE WAY.

EGL 5.900

2m 100mm Duct

GIVE WAY

WHITE THERMOPLASTIC LINE MARKING.

Remove existing trees.

Remove existing fences.

EXISTING CARPARK.

STOP

FOOTPATH.

STATION ROAD.

FORM NEW PATH IN MACADAM WITH RAMP AS SHOWN