



COMHAIRLE CONTAE CHILL MHAINTÁIN Wicklow County Council

Pleanáil, Forbairt Eacnamaíochta agus Tuaithe Planning, Economic and Rural Development

Áras An Chontae / County Buildings
Cill Mhantáin / Wicklow
Guthán / Tel (0404) 20148
Faics / Fax (0404) 69462
Rphost / Email plandev@wicklowcoco.ie
Suíomh / Website www.wicklow.ie

Ross Wilson,
c/o Buttle Design & Planning Consultants,
Main Street,
Carnew,
Co. Wicklow.

5th of October 2026

RE: Declaration in accordance with Section 5 of the Planning & Development Acts
2000 (As Amended) -EX114/2026

A Chara,

I enclose herewith Declaration in accordance with Article 5 (2) (A) of the Planning & Development Act 2000.

Where a Declaration is used under this Section any person issued with a Declaration under subsection (2) (a) may, on payment to An Coimisiún Pleanála of such fee as may be prescribed, refer a declaration for review by the Coimisiún within four weeks of the date of the issuing of the declaration by the Local Authority.

Is mise, le meas,

pp Stáinne Byrne

ADMINISTRATIVE OFFICER
PLANNING DEVELOPMENT & ENVIRONMENT.





Comhairle Contae Chill Mhantáin Wicklow County Council

Pleanáil, Forbairt Eacnamaíochta agus Tuaithe Planning, Economic and Rural Development

Áras An Chontae / County Buildings
Cill Mhantáin / Wicklow
Guthán / Tel. (0404) 20148
Faics / Fax (0404) 69462
Rphost / Email plandev@wicklowcoco.ie
Suíomh / Website www.wicklow.ie

DECLARATION IN ACCORDANCE WITH ARTICLE 5 (2) (A) OF THE PLANNING & DEVELOPMENT ACT 2000 AS AMENDED

Applicant: Ross Wilson

Location: The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow

Reference Number: EX114/2026

CHIEF EXECUTIVE ORDER NO. CE/PERD/2026/1202

A question has arisen as to whether "*the installation of slatted tank in farmyard*" at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow is or is not exempted development.

Having regard to:

- a) The details received with the Section 5 Declaration Application on 14/09/2026
- b) Sections 2, 3 and 4 of the Planning & Development Act 2000 (as amended)
- c) Article 6, 9, and Schedule 2: Part 3: Class 6A of the Planning and Development Regulations 2001 (as amended).

Main Reasons with respect to Section 5 Declaration:

- iv. The installation of a slatted tank would come within the meaning of works as set out in Section 2 of the Planning and Development Act 2000 (as amended).
- v. These works are development having regard to the provisions of Section 3 of the Planning and Development Act 2000 (as amended).
- vi. The slatted tank would not come within the description and limitations as set out under Schedule 2, Part 3, Class 6A, of the Planning and Development Regulations 2001 (as amended) as the proposed structure shall be situated within 100 metres of no.2 dwellings which are not identified as being in the ownership of the person providing the structure and from which no written consent to carry out the identified works has been provided. In addition it has not been confirmed that the proposed tank shall be constructed in accordance with relevant Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements / specifications, shall have regard to the need to avoid water pollution, or shall provide, as appropriate, the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety.

The Planning Authority considers that is development and is Not exempted development
at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow

Signed: Deanne Byrne
PP ADMINISTRATIVE OFFICER

Date: 30/09/2026

PLANNING DEVELOPMENT & ENVIRONMENT



WICKLOW COUNTY COUNCIL

PLANNING & DEVELOPMENT ACTS 2000 (As Amended)
SECTION 5

CHIEF EXECUTIVE ORDER NO. CE/PERD/2026/1202

Reference Number: EX114/2026

Name of Applicant: Ross Wilson

Nature of Application: Section 5 Referral as to whether "*the installation of a slatted tank in farmyard*" is or is not development and is or is not exempted development.

Location of Subject Site: The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow

Report from: Billy Slater A.P.

With respect to the query under Section 5 of the Planning & Development Act 2000 as to whether "*the installation of a slatted tank in farmyard*" at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow is or is not exempted development within the meaning of the Planning & Development Act 2000 (as amended)

Having regard to:

- a) The details received with the Section 5 Declaration Application on 14/09/2026
- b) Sections 2, 3 and 4 of the Planning & Development Act 2000 (as amended)
- c) Article 6, 9, and Schedule 2: Part 3: Class 6A of the Planning and Development Regulations 2001 (as amended).

Main Reasons with respect to Section 5 Declaration:

- i. The installation of a slatted tank would come within the meaning of works as set out in Section 2 of the Planning and Development Act 2000 (as amended).
- ii. These works are development having regard to the provisions of Section 3 of the Planning and Development Act 2000 (as amended).
- iii. The slatted tank would not come within the description and limitations as set out under Schedule 2, Part 3, Class 6A, of the Planning and Development Regulations 2001 (as amended) as the proposed structure shall be situated within 100 metres of no.2 dwellings which are not identified as being in the ownership of the person providing the structure and from which no written consent to carry out the identified works has been provided. In addition it has not been confirmed that the proposed tank shall be constructed in accordance with relevant Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements / specifications, shall have regard to the need to avoid water pollution, or shall provide, as appropriate, the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety.

Recommendation

The Planning Authority considers that "*the installation of slatted tank in farmyard*" is development and is Not exempted development at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow recommended in the planning reports.

Signed: Declan Byrne.

Date: 30/09/2026

ORDER:

I HEREBY DECLARE: That "*the installation of a slatted tank in farmyard*" is development and is Not exempted development at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow within the meaning of the Planning & Development Acts 2000 (as amended).

Signed: Neil Gormley

T/Senior Planner

Planning, Economic & Rural Development

Date: 2/10/2026



**WICKLOW COUNTY COUNCIL
PLANNING DEPARTMENT**

To:	Edel Bermingham A/S.P. / Patrice Ryan S.E.P.
From:	Billy Slater A.P.
Type:	Section 5 Application
REF:	EX 114/2026
Applicant:	Ross Wilson
Date of Application:	14/09/2026
Decision Due Date:	11/10/2026
Address:	The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow
Exemption Query:	Installation of slatted tank in farmyard.

Application Site:

The application site is located some 1.3km southwest of the level 8 Rural Settlement of Donaghmore and 1.5km east of the village of Stratford-on-Slaney within the rural townland of Ballintruer More. The site comprises of an existing agricultural complex with an adjoining dwelling and neighbouring farmyard present to the southwest. The area is predominantly agricultural in nature. The subject site is accessed via no.2 vehicular entrances off of the L-8296-0 Local Road.

Aerial / Site Image



Relevant Planning History:

Ref	07/529
Applicant	Walton Wilson
Development	Construction of new 312 m2 extension to existing 774m2 shed to cover existing holding yard and slurry pit, all ancillary works associated with above
Decision	Grant
Ref	92/8383
Applicant	Robert Wilson
Development	cubicle house, roofed yard, easy fee system & lean-to
Decision	Grant
Ref	87/3171
Applicant	Robert Isaac Wilson
Development	extension to dwelling house
Decision	Grant

Question:

With respect to the query under Section 5 of the Planning and Development Act 2000 (as amended), as to whether the;

- Installation of slatted tank in farmyard.

at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow is or is not exempted development:

Legislative Context:

Planning and Development Act 2000 (as amended)

Section 2(1) of the Act states the following in respect of the following:

“structure” means any building, structure, excavation, or other thing constructed or made on, in or under any land, or any part of a structure so defined, and—

(a) where the context so admits, includes the land on, in or under which the structure is situate, and

“works” includes Any act or operation of construction, excavation, demolition, extension, alteration, repair or renewal...”

Section 3(1) of the Act states the following in respect of ‘development’:

“In this Act, ‘development’ means, except where the context otherwise requires, the carrying out of any works on, in, over or under land or the making of any material change in the use of any structures or other land.”

Section 4 sets out the types of works that while considered ‘development’, can be considered ‘exempted development’ for the purposes of the Act.

Section 4 (1) (h) states:

“development consisting of the carrying out of works for the maintenance, improvement or other alteration of any structure, being works which affect only the interior of the structure or which do not materially affect the external appearance of the structure so as to render the appearance inconsistent with the character of the structure or of neighbouring structures.”

Section 4(2) makes provision for ministerial regulations to set out further exemptions. The 2001 Planning Regulations as amended derive from this section and designate further works as being exempted development for the purposes of the act.

Planning and Development Regulations, 2001 (as amended)

Article 6(1) states that certain classes of development which are specified in Schedule 2 shall be exempted development for the purposes of the Act, subject to compliance with any associated conditions and limitations;

Article 9(1) (a) and (b) details a number of circumstances under which the development to which Article 6 relates shall not be exempted development for the purposes of the Act.

Schedule 2, Part 3 outlines classes of exempt development in the rural area as well as associated conditions and limitations. The following are of relevance.

CLASS 6A

Works consisting of a structure for the storage of slurry, effluent or soiled water collected from agricultural buildings, agricultural farmyards and any ancillary provision to aid in the handling of the slurry, effluent or soiled water.

Limitations / Conditions

1. No such structure shall be used for any purpose other than the purpose of agriculture.
2. The maximum storage capacity of any such storage facility shall not exceed 1000 cubic metres.
3. The aggregate capacity of tanks, situated within the same farmyard complex, shall not exceed 1,500 cubic metres.
4. The structure having regard to its size, use and location shall be constructed in accordance with Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements and shall have regard to the need to avoid water pollution. The structure shall not be an earth lined Slurry/Effluent Store.
5. No such structure shall be situated, and no effluent from such structure shall be stored, within 10 metres of any public road.
6. No such structure within 100 metres of any public road shall exceed 8 metres in height.
7. No such structure shall be situated, and no effluent from such structure shall be stored, within 100 metres of any house (other than the house of the person providing the structure) or other residential building or school, hospital, church or building used for public assembly, save with the consent in writing of the owner and, as may be appropriate, the occupier or person in charge thereof.
8. No such structure shall be constructed within a flood zone identified in statutory land use plans as Flood Zone A or Flood Zone B or where the probability of flooding is moderate to high or erosion control zone.
9. No such structure shall be within 60 metres of a public or private water source.
10. No such structure shall be situated, at the closest point, less than 50 metres from a water course or water body in the case of new farmyards, and not less than 10m in the case of extensions/modifications to an existing facility.
11. All such tanks shall be constructed in accordance with the relevant specification published by the Department of Agriculture, Food and the Marine in force at the time of construction of the tank.
12. No unpainted metal sheeting shall be used for roofing or on the external finish of the structure.
13. The use of this Class of exemption requires a declaration from the relevant Planning authority under section 5 of the Principal Act, declaring the exemption is applicable prior to commencement of construction.
14. Ancillary provision shall include as appropriate the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety.

Details submitted in support of the application:

- Section 5 Application Form
- Site Identification Map / Land Reg Compliant Map
- Site Layout Plan

Assessment:

The Section 5 declaration application seeks an answer with respect to the following question:

Whether the;

- Installation of slatted tank in farmyard.

at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow, is or is not exempted development:

The structure subject of the referral is located within the level 10 rural area. The development site is not located in the curtilage of any Protected Structure.

The first assessment must be whether or not the proposal outlined above constitutes development within the remit of Section 3 of the Planning and Development Act 2001. In this regard, Section 3 of the Planning and Development Act provides that:

“development” means, except where the context otherwise requires, the carrying out of any works on, in, over or under land or the making of any material change in the use of any structures or other land.

It should be noted that Section 2 of the Act defines works as:

“works” includes any act or operation of construction, excavation, demolition, extension, alteration, repair or renewal and, in relation to a protected structure or proposed protected structure, includes any act or operation involving the application or removal of plaster, paint, wallpaper, tiles or other material to or from the surfaces of the interior or exterior of a structure.

I am satisfied that the proposal would involve works of construction and excavation and therefore the proposal does constitute development.

The second stage of the assessment is to determine whether or not the proposal would be exempted development under the Planning and Development Act 2000 (as amended) or its associated Regulations. Schedule 2, Pt.3 Class 6A of the Planning and Development Regulations 2001 (as amended) states that the following constitutes exempted development:

Works consisting of a structure for the storage of slurry, effluent or soiled water collected from agricultural buildings, agricultural farmyards and any ancillary provision to aid in the handling of the slurry, effluent or soiled water.

The proposed works, inclusive of the provision no.2 slatted tanks of some 232.28m³ each, is considered to fall under the description of Schedule 2, Pt.3 Class 6A of the Planning and Development Regulations 2001 (as amended). The following checklist will determine if the development complies with the associated conditions and limitations of Class 6A.

<i>1. No such structure shall be used for any purpose other than the purpose of agriculture.</i>	Yes – stated use for agriculture.
<i>2. The maximum storage capacity of any such storage facility shall not exceed 1000 cubic metres.</i>	Yes – two slatted tanks of 232.28m ³ proposed for total of 464.56m ³
<i>3. The aggregate capacity of tanks, situated within the same farmyard complex, shall not exceed 1,500 cubic metres.</i>	Yes – total aggregate capacity of tanks (including that proposed) = 1,141.02m ³
<i>4. The structure having regard to its size, use and location shall be constructed in accordance with Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements and shall have regard to the need to avoid water pollution. The structure shall not be an earth lined Slurry/Effluent Store.</i>	Unknown – It has not been confirmed that the proposed slatted tank is to be constructed in accordance with Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements and shall have regard to the need to avoid water pollution. The proposed slatted tank is not ‘earth lined’ as per submitted section A-A.

5. No such structure shall be situated, and no effluent from such structure shall be stored, within 10 metres of any public road.	Yes- structure is in excess of 10 metres from any public road.
6. No such structure within 100 metres of any public road shall exceed 8 metres in height.	Yes- structure does not exceed 8m in height.
7. No such structure shall be situated, and no effluent from such structure shall be stored, within 100 metres of any house (other than the house of the person providing the structure) or other residential building or school, hospital, church or building used for public assembly, save with the consent in writing of the owner and, as may be appropriate, the occupier or person in charge thereof.	No – Proposed tank is located within 100m from an adjoining dwelling located 45m to the south-east and a dwelling house located 65m to the north-west, neither of which are which are, per land registry details via 'landdirect.ie', the house of the person providing the structure. No consent from third parties has been provided.
8. No such structure shall be constructed within a flood zone identified in statutory land use plans as Flood Zone A or Flood Zone B or where the probability of flooding is moderate to high or erosion control zone.	Yes – Site is not identified as being located within a designated Flood Zone, nor is the probability of flooding deemed to be moderate to high. The development site is also not located within an erosion control zone
9. No such structure shall be within 60 metres of a public or private water source.	Yes – Per the submitted layout plan the proposal is not within 60 metres of a public or private water source.
10. No such structure shall be situated, at the closest point, less than 50 metres from a water course or water body in the case of new farmyards, and not less than 10m in the case of extensions/modifications to an existing facility.	Yes – structure is not located within 50 metres from a water course or water body.
11. All such tanks shall be constructed in accordance with the relevant specification published by the Department of Agriculture, Food and the Marine in force at the time of construction of the tank.	Unknown – It has not been stated if the tanks are to be constructed in accordance with the relevant specification published by the Department of Agriculture, Food and the Marine in force at the time of construction of the tank.
12. No unpainted metal sheeting shall be used for roofing or on the external finish of the structure.	Yes – no roofing proposed.
13. The use of this Class of exemption requires a declaration from the relevant Planning authority under section 5 of the Principal Act, declaring the exemption is applicable prior to commencement of construction.	Non applicable to assessment.
14. Ancillary provision shall include as appropriate the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety.	Unknown – It has not been confirmed that ancillary provision shall include as appropriate the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety

It is noted that the proposed works to which article 6 relates shall not be exempted development for the purposes of the Act if the carrying out of such works would contravene with the limitations as set out per **Article 9 (1)**.

Recommendation:

With respect to the query under Section 5 of the Planning and Development Act 2000 (as amended), as to whether or not the proposal for the:

- Installation of slatted tank in farmyard

at The Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow is or is not exempted development.

The Planning Authority considers that:


The installation of a slatted tank in an existing farmyard at the Old Grazing, Ballintruer More, Baltinglass, Co. Wicklow **is development and is NOT exempted development**

Main Considerations with respect to Section 5 Declaration:

- a) The details received with the Section 5 Declaration Application on 14/09/2026
- b) Sections 2, 3 and 4 of the Planning & Development) Act 2000 (as amended)
- c) Article 6, 9, and Schedule 2: Part 3: Class 6A of the Planning and Development Regulations 2001 (as amended).


Main Reasons with respect to Section 5 Declaration:

- i. The installation of a slatted tank would come within the meaning of works as set out in Section 2 of the Planning and Development Act 2000 (as amended).
- ii. These works are development having regard to the provisions of Section 3 of the Planning and Development Act 2000 (as amended).
- iii. The slatted tank would not come within the description and limitations as set out under Schedule 2, Part 3, Class 6A, of the Planning and Development Regulations 2001 (as amended) as the proposed structure shall be situated within 100 metres of no.2 dwellings which are not identified as being in the ownership of the person providing the structure and from which no written consent to carry out the identified works has been provided. In addition it has not been confirmed that the proposed tank shall be constructed in accordance with relevant Department of Agriculture, Food and the Marine and Department of Housing, Local Government and Heritage requirements / specifications, shall have regard to the need to avoid water pollution, or shall provide, as appropriate, the installation of any signage, fencing or other safety infrastructure as recommended by the Health and Safety Authority regarding Slurry Safety.



Billy Slater A.P.

29/09/2026


21/11/2028.

MEMORANDUM

WICKLOW COUNTY COUNCIL


TO: Billy Slater
Assistant Planner

FROM: Joanne Byrne
A/Staff Officer

RE:- EX114/2026 - Declaration in accordance with Section 5 of the Planning & Development Acts 2000 (as amended)

I enclose herewith for your attention application for Section 5 Declaration received 14/09/2026.

The due date on this declaration is the **11/10/2026**.



A/ Staff Officer
Planning, Development & Environment



Comhairle Contae Chill Mhantáin Wicklow County Council

**Pleanáil, Forbairt Eacnamaíochta agus Tuaithe
Planning, Economic and Rural Development**

Áras An Chontae / County Buildings
Cill Mhantáin / Wicklow
Guthán / Tel (0404) 20148
Faics / Fax (0404) 69462
Rphost / Email plandev@wicklowcoco.ie
Suíomh / Website www.wicklow.ie

Ross Wilson,
C/o Buttle Design & Planning Consultants,
Main Street,
Carnew,
Co. Wicklow

14th of September 2026

**RE: Application for Certificate of Exemption under Section 5 of the Planning and
Development Acts 2000 (as amended) – EX114/2026**

A Chara

I wish to acknowledge receipt on 14/09/2026 full details supplied by you in respect of the
above Section 5 application. A decision is due in respect of this application by
11/10/2026.

Mise, le meas

Joanne Byrne
A/ Staff Officer
Planning, Economic & Rural Development



Wicklow County Council
County Buildings
Wicklow
0404-20100

14/09/2026 09 29 15

Receipt No L1/0/369652
***** REPRINT *****

BUTTLE DESIGN & PLANNING CONSULTAN
MAIN STREET
CARNEW
CO WICKLOW

PLANNING APPLICATION FEES	80 00
GOODS	80 00
VAT Exempt/Non-vatable	

Total	80 00 EUR
-------	-----------

Tendered	
Cheque	80 00
ROSS WILSON	

Change	0.00
--------	------

Issued By Samantha Duffy
From Customer Service Hub
Vat reg No 0015233H




Wicklow County Council
County Buildings
Wicklow
Co Wicklow
Telephone 0404 20148
Fax 0404 69462

Office Use Only

Date Received _____

Fee Received _____

**APPLICATION FORM FOR A
DECLARATION IN ACCORDANCE WITH SECTION 5 OF THE PLANNING &
DEVELOPMENT ACTS 2000(AS AMENDED) AS TO WHAT IS OR IS NOT
DEVELOPMENT OR IS OR IS NOT EXEMPTED DEVELOPMENT**



1. Applicant Details

- (a) Name of applicant: Ross Wilson
Address of applicant: "The Old Grazing", Ballintruer More,
Baltinglass, Co. Wicklow. W91 K03D.

Note Phone number and email to be filled in on separate page.


2. Agents Details (Where Applicable)

- (b) Name of Agent (where applicable) Thomas Buttle
Address of Agent : Buttle Design & Planning Consultants Ltd.
Main Street, Carnew, Co. Wicklow.

Note Phone number and email to be filled in on separate page.

3. Declaration Details

- i. Location of Development subject of Declaration:
Ballintruer More, Baltinglass., Co. Wicklow.



- ii. Are you the owner and/or occupier of these lands at the location under i. above ?
Yes/ No.

YES

- iii. If 'No' to ii above, please supply the Name and Address of the Owner, and or occupier

N/A

- iv. Section 5 of the Planning and Development Act provides that : If any question arises as to what, in any particular case, is or is not development and is or is not exempted development, within the meaning of this act, any person may, on payment of the prescribed fee, request in writing from the relevant planning authority a declaration on that question. You should therefore set out the query for which you seek the Section 5 Declaration:

If the Installation of a slatted tank and all associated works in my farmyard is considered an exempt development

Additional details may be submitted by way of separate submission.

- v. Indication of the Sections of the Planning and Development Act or Planning Regulations you consider relevant to the Declaration:

Class 6A of the Planning & Development (Act of 2000) (No. 2) Regulations

Additional details may be submitted by way of separate submission.

- vi. Does the Declaration relate to a Protected Structure or is it within the curtilage of a Protected Structure (or proposed protected structure) ?

NO

vii. List of Plans, Drawings submitted with this Declaration Application:

EX01 – Plan & Section (Slatted Tanks A & B)

EX02 – Site Layout Map

EX03 – Site Location Maps

viii. Fee of € 80 Attached ? **Yes**

Signed:


A handwritten signature in black ink, appearing to be 'TLBA', is written over a horizontal line.


Dated :

11th September 2026


PART OF OS MAP: 4010 - D (Digital)

SITE LOCATION MAP (Scale: 1:2500)

PART OF OS MAP: 4010 - D (Digital)



Buttle
Design & Planning Consultants Ltd.
27 MAIN STREET, CARNEW, CO. WICKLOW.
TEL: (053) 9426961
E-MAIL: buttleplanning@gmail.com



OUTPUT SCALE: 1:2,500

CAPTURE RESOLUTION:
The map objects are only accurate to the resolution at which they were captured.
Output scale is not indicative of data capture scale.
Further information is available at:
www.tailte.ie; search 'Capture Resolution'

LEGEND:
To view the legend visit
www.tailte.ie and search for
'Large Scale Legend'

SCALES:	1:2500, 1:10560	CLIENT:	Ross Wilson, Ballintruer More, Baltinglass, Co. Wicklow.
SHEET NO.:	EX03		
DRAWING:	SITE IDENTIFICATION MAP SITE LOCATION MAP	TITLE:	Installation of an outdoor slatted tank and all associated works in my farmyard at Ballintruer More, Baltinglass, Co. Wicklow.

NOTES

1. Existing slatted tank.

2. Existing slatted tank.

3. Existing slatted tank.

4. Existing s.

5. Proposed slatted tank in existing farmyard.

6. Existing shed.

7. Existing straw bedded shed.

8. Existing dwellinghouse.

9. Existing agricultural sheds.

10. Existing agricultural shed.

11. Existing agricultral shed.

12. Existing agricultural shed.

13. Existing outhiuse.

14. Existing Derelict Dwelling.


15. Existing site boudaries.

LEGEND

Proposed Slatted Tanks


Existing Slatted Tanks

SITE AREA = 0.499 Ha



Buttle
Design & Planning Consultants Ltd.
27 MAIN STREET, CARNEW, CO. WICKLOW.
TEL: (053) 9426961
E-MAIL: buttleplanning@gmail.com

CLIENT:	Ross Wilson, Ballintruer More, Baltinglass, Co. Wicklow.
TITLE:	Installation of a slatted tank and all associated works in my farmyard at Ballintruer More, Baltinglass.
DRAWING:	SITE LAYOUT PLAN.
SCALES:	1:500
SHEET No:	EX02



FLOOR PLAN
FLOOR AREA = 208.4sq.m


CAPACITY OF PROPOSED SLATTED TANKS
(INTERNAL DIMENSIONS):

SLATTED TANK A	= 27.2m X 3.5 X 2.44	= 232.28M3
SLATTED TANK B	= 27.2m X 3.5 X 2.44	= 232.28M3

CAPACITY OF EXISTING STORAGE FACILITIES
(INTERNAL DIMENSIONS):

SLATTED TANK 1	= 28.9m X 2.89 X 2.7	= 225.50M3
SLATTED TANK 2	= 4.57m X 1.98 X 1.37	= 23.39M3
FLOW CHANNEL	= 18.3m X 2.89 X 1.21	= 63.99M3
SLATTED TANK 3	= 8.61m X 2.89 X 1.00	= 24.88M3
COVERED SLURRY PIT	= 18.28m X 12.19 X 1.52	= 338.70M3

TOTAL TANK CAPACITY = 1,141.02M3



EXEMPTION DRAWING



Buttle

Design & Planning Consultants Ltd.
27 MAIN STREET, CARNEW, CO. WICKLOW.
TEL: (053) 9426961

E-MAIL: buttleplanning@gmail.com

SCALES:

1:100

SHEET NO.:

EX01

DRAWING:

PLAN & SECTION
(SLATTED TANKS A&B)

CLIENT:

Ross Wilson,
Ballintruer More, Baltinglass,
Co. Wicklow.

TITLE:

Installation of a slatted tank and all associated
works in my farmyard at Ballintruer More,
Baltinglass, Co. Wicklow.